

Morongo Valley Fire Station Price from Helfman Construction

Travis Helfman <travishelfman@gmail.com>

Thu 11/9/2023 4:50 PM

To:Brittany Chavez <b.chavez@morongovalleyfire.org>

Helfman Construction

General Contractor

CA Lic # 557768

[760-221-3328](tel:760-221-3328)

Estimate

Morongo Valley Fire Station

Demo - Labor to demo walls as described in before and after floor plans. Labor to demo all flooring

\$4,500.00

Plumbing - Labor and materials to cap off plumbing at 2nd bathroom below concrete and behind walls.

\$2,450.00

Framing - Labor and materials to frame new door openings, frame as needed to eliminate dropped ceilings and all other miscellaneous framing needed such as drywall backing, necessary headers, etc...

\$3,800.00

Electrical - Labor and materials to remove old wiring as needed. Labor and materials to add new wiring for outlets, switches and recessed lighting. Includes all can lights and trim.

\$9,936.00

Insulation - Labor and materials to install R19 insulation to all ceilings.

\$3,150.00

Drywall - Supply and install 1/2" drywall for all ceilings and to all walls as needed. Includes tape and orange peel texture.

\$7,600.00

Flooring - Labor and materials to install laminate Flooring.

\$8,900.00

Painting - Labor and materials to prep, prime and paint walls, ceilings and doors.

\$8,950.00

Doors - Supply and install doors as per plans.

\$1,950.00

Stucco - Patch stucco as needed at old door opening.

\$500.00

Contractor overhead Fee

\$6,800.00

Total

\$58,536.00

Note : Does not include baseboards.

- Does not include anything that is not mentioned in above scope.

Caution: This is an external email and may be malicious. Please take care when clicking links or opening attachments. If you have any questions, please contact IT.